

Kemtile at Coca Cola

In 2 to 3 week phases, starting in February 2008 and completing the final phase nine months later in October, Kemtile have undertaken a major overhaul of the syrup tank room at Coca Cola East Kilbride. The job at was far from straightforward, mainly because it is a very awkward and congested area. The work was split into 3 sections. Coca Cola Enterprises removed the tanks and plant from each section in turn.



Starting in area 1, Luddon Construction removed the old flooring and wall finish to a height of 500mm before Kemtile moved on to site. Kemtile then installed a membrane to both the walls and the floor and constructed two drainage channels running the full length of the room. Having completed the substrate, Kemtile installed 200 square metres of Kagetec GFK ceramic flooring system using Amsterdam R11 slip resistant hexagonal tiles. The tanks were then moved into the completed area and the next area was released.

"Kemtile have provided us with a first class service in the revamp of our processing area, the high standards Kemtile set has played a major part in the transformation of the building. Kemtile completed all works in a timely, safe manner working well with the constraints placed upon them given the sensitivity of the area." Paul Dolan, Technical Manager, Coca Cola Enterprises Ltd

Kemtile will be returning in 2009 to do additional work at the facility. Kemtile have worked for almost every major brand in the food and drink industry. They understand this very exacting industry, respect its constraints and appreciate its specific needs. When your manufacturing facility demands the highest hygiene standards, to budget and on time call Kemtile on 01925 763045, email all@kemtile.co.uk or go www.kemtile.co.uk.

<<ENDS>>

290 words

This press release was issued on 19th November 2008 on behalf of Kemtile Ltd by JBK Marketing Limited. For further information email judi@jbkmarketing.co.uk